

CHITALDRUG DIVISION.

Dated 25th February 1918.

1. Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer Chitaldrug Division, up to 20th March 1918, for constructing a Local Fund combined Dispensary and in-patient ward with out-houses at Challakere. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Local Fund Dispensary and in-patient ward with out-houses at Challakere," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Superintending Engineer, Northern Circle, Bangalore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of constructing a Local Fund Dispensary and In-patient ward with out-houses at Challakere, Chitaldrug District.

No.	Items of work	Per	Quantity
1	Earthwork excavating foundation and filling basement including watering and tamping.	C. yd.	182
2	Burnt stone in mortar filling foundation and basement.	C. ft.	4,787
3	Burnt brick in mortar superstructure.	"	6,342
4	Burnt stone slabs 6" thick nicely dressed.	S. ft.	870
5	Cut stone pillars nicely dressed 9" x 9" x 7' high with bases and capitals, etc., complete.	Each	13
6	Ornamental cut stone cantilivers below gable triple windows.	"	4
7	Plastering with chunam.	Sq. ft.	9519
8	White and colour washing two coats.	"	9519
9	Cement pointing to basement.	"	6'63
10	Teakwood wrought and put up with wood oiling.	C. ft.	10417
11	Teakwood pannelled door including bolts hinges brass lock porcelain knobs and iron clamps, etc.	S. ft.	304
12	Teakwood windows inside glazed and pannelled outside including 1/2" iron bars bolts, hinges and iron clamps, hooks, etc.	"	225
13	Teakwood ventilators with glazed shutters iron clamps, hooks, cotton, ropes, etc., complete.	"	90
14	Teakwood triple windows with glazed shutters iron clamps for frames, etc., complete.	"	32
15	Flooring with 1st class Mangalore tiles 9" x 9" or 3" concrete bed and cement pointing, etc., complete.	Sq. ft.	6'92
16	Flooring with Cuddapa slabs on 3" concrete bed and cement pointing, etc., complete.	"	8'24
17	Silicate painting to doors and windows and ventilators, complete.	"	7'45
18	Wood oiling two coats.	"	6'85
19	Roofing with 1st class Mangalore tiles on teak reepers, etc., complete.	"	32'94
20	Ornamental ridge tiles set in mortar, etc., complete.	R. ft.	103
21	Plain ridge tiles set in mortar.	"	31
22	Teakwood eave board ornamental 9" wide with painting, etc., complete.	"	442
23	Teakwood pendants.	Each	18
24	Teakwood ornamental finials big-main hall.	"	2
25	Do small.	"	2
26	Teakwood sun shades in rear.	"	8
27	Binding wall at gable ends 1' foot inside and 9" thick with burnt brick in chunam and smooth plastering.	R. ft.	147
28	Zinc sheet for valleys.	S. ft.	92
29	Teakwood planking 1/2" thick for valley.	"	92
30	Clearing site and levelling ground.	Lump sum	
31	Inscription of name in the front gable and date moulding works, etc.	Lump sum	
32	Tarring wood work two coats.	Lump sum	6'00
33	Ventilating tiles.	Each	4
34	Coping with burnt brick in chunam and plastering.	R. ft.	39
35	Constructing a cistern.	Each	1

N. ANANDALWAR,
Executive Engineer.